


LOCATION E - GENERAL ARRANGEMENT - COLCHESTER AVENUE
SCALE 1:100 @ A1

- KEY**
- PROPOSED AREA OF CARRIAGEWAY TO BE PLANED 40mm AND RESURFACED WITH 40mm AC10 CLOSE SURFACE COURSE PMB 75-130/75 TO BS 13108-1 MIN 65PSV
 - PROPOSED FLEXIBLE FOOTWAY CONSTRUCTION TYPE 2: AC20 DENSE BINDER COURSE 100/150REC 50mm THICK; AC6 SURFACE COURSE 1260/220 25mm THICK.
 - PROPOSED FLEXIBLE FOOTWAY CONSTRUCTION TYPE 1: TYPE 1 SUB-BASE 150mm THICK; AC20 DENSE BINDER COURSE 100/150REC 50mm THICK; AC6 SURFACE COURSE 1260/220 25mm THICK.
 - CARRIAGEWAY TO BE REINSTATED. 300mm FROM FRONT FACE OF KERB WITH HOT BITUMEN SEAL OVER BANDING. 75mm SPEED TABLE TO BE INSTALLED. REFER TO DRAWING 008.
 - PROPOSED 400x400x65mm PRECAST CONCRETE TACTILE PAVING SLABS COLOUR RED. SURROUNDED BY 150 x 50mm PATH EDGING. REFER TO DRAWING 008.
 - PROPOSED 400x400x65mm PRECAST CONCRETE TACTILE PAVING SLABS COLOUR BUFF. SURROUNDED BY 150 x 50mm PATH EDGING. REFER TO DRAWING 008.
 - PROPOSED MODUSTAR BELISHA BEACON. REFER TO DRAWING 008.
 - PROPOSED PERMANENT BOLLARD POLYURETHANE NON-ILLUMINATED GLADSON MANCHESTER, REBOUND, LOCKFAST SOCKET. WITH RED AND WHITE MICROPRISMATIC REFLECTIVE STRIPS. 2 x 12.5mm & 1 x 63mm. TO BE INSTALLED MINIMUM OF 450mm FROM THE EDGE OF CARRIAGEWAY.
 - PROPOSED KERB LINE.
 - GRASSED AREA TO REMAIN.
 - GLADSON SIGMASTER BOLLARD WITH DIAG 610L.
 - TK TRANSITION KERB
 - DK DROPPED KERB
 - BN BULLNOSE KERB
 - QK QUADRANT KERB

NOTES: ALL ROAD MARKINGS TO COMPLY WITH THE TSRGD 2016 & CHAPTER 5 OF THE TRAFFIC SIGNS MANUAL.
ALL ROAD MARKINGS TO BE TIED TO EXISTING.



COPYRIGHT OF THE CITY OF CARDIFF COUNCIL. ALL RIGHTS RESERVED.
 DRAWING CAN BE SCALED FOR PLANNING APPLICATION PURPOSES ONLY.
 © Crown copyright and database right (2011) Ordnance Survey 100023576.
 © Havillan, S. Crown & Havillan crmha ddan (2011) Xswng, Ordman 100023576.

UKAS QUALITY MANAGEMENT
 FS 25745

DESIGN CONTRACTS AND DELIVERY
 DYLUNO CONTRACTAU A DARPARAU
Andrew Gregory
 DIRECTOR FOR CITY SERVICES
 CYFARIANTDWR GRASNAWETHAUR DDINAS

Rev	By	Date	Description of Amendment

FOR TENDER

Project	HOWARDIAN PRIMARY SCHOOL SCHOOL SAFETY ZONE
The	COLCHESTER AVENUE & LOCATION PLAN
Drawn	NT
Checked	TG
Scale	A5 SHOWN
Date	03/2018
Project Number	CO17003
Drawing Number	003
County Hall, Atlantic Wharf, Cardiff CF10 4UW	Telephone 029 287 2456

CYNGOR DINAS CAERDYDD THE CITY OF CARDIFF COUNCIL